



BUILDING EXPERTS & CONSULTANTS

Engineers, Architects, Planners, Builders & Management Consultants

ESTIMATION & COSTING

GROUND FLOOR(2300 sft of 5500sft)

Date:24/03/2022

CLIENT-Rais-Shamsun Markajun Madina Hafijia Madrasa & Orphanage , Patta Sorif R/A, Sankhola Union, Upazila-Chunarughat,District-Habiganj.

S/N	Items	Quantity	Units	Rate(Tk)	Amount(Tk)
1	Precast Pilling (Material+ Labour Cost)		Pcs		0
2	RCC Work(Base to Roof)				
	Cement (including Carrying cost)	688	Bags	520	357760
	Sand (including Carrying cost)	1750	Cft	45	78750
	Khoa (including Carrying cost)	3500	Cft	130	455000
	Rod(Steel bar) (including Carrying cost)	9208	Kg	95	874760
	Chemical admixture	50	Litres	165	8250
3	Sand Filling (EGL to PL)	115	Gari	2500	287500
4	Brick Work(Solling,Wall, S.tank etc.)/Plaster				
	Bricks (including Carrying cost)	20487	Pcs	10	204870
	Cement (including Carrying cost)	272	Bags	520	141440
	Sand (including Carrying cost)	1360	Cft	45	61200
	Chemical admixture	68	Litres	165	11220
5	Grill Work (for Window)	315	Sft	400	126000
6	Doors & Window				
	Doors(Wood + Making, Fitting Charge)	5	Pcs	15000	75000
	Windows(Wood + Making, Fitting Charge)	315	Pcs	300	94500
7	Electrical Work(Goods+Labour Charge)				70000
8	Sanatary Work(Goods+Labour Charge)				50000
9	Tiles Work(Floors, Bath, Stair etc.)	2300	Sft	150	345000
10	Coloring (Inside & Outside)	6000	Sft	10	60000
11	Deep Tubewell	1	No's	150000	150000
Total Amount(BDT)=					3451250
In Words-Thirty Four Lakh Fifty One Thousand Two Hundred Fifty Taka					

Khan Md. Monzur Elahi

Engr. Md. Al Monwar
B.Sc. Engr.(Civil & Environment)
SUST. MIEB-M27014

Business Address: Thinkuna Pukurpar,
Habigtanj Sadar, Habiganj, Bangladesh.

Mobile/Phone:+88-01737505193, E-mail: building.hbg@gmail.com